


**Three Rivers Diving LLC**

310 River Ave  
 Belle Vernon, PA 15012 US  
 threeriversdivingllc@gmail.com



**PROPOSAL**

ADDRESS  
**TARENTUM WATER PLANT**  
 618 East 5th Avenue  
 Tarentum, PA 15084

PROPOSAL 24-12  
 DATE 04/05/2024

DESCRIPTION/PROPOSAL Pump House Maintenance	LOCATION/PURCHASE ORDER Tarentum Pump House	VESSEL/BARGE N/A
--	--	---------------------

DESCRIPTION	AMOUNT
Job Location: Tarentum Pump House	0.00
Job Description: Pump house maintenance.	0.00
Job Proposal: Three Rivers Diving proposes the continuation of maintaining an open intake inlet from the river to the pump house.	0.00
This proposal has three (3) areas of attention that needs to be addressed:	0.00
1. Continuation of maintaining an open inlet from river to pump house.	0.00
2. The pump house outside wells need to be cleaned out to allow a good flow as well as to allow a camera to be placed into the manifold to see whether or not it is full of material. There is a Part B to this IF the manifold is full. This would involve plugging intakes to isolate manifold so it could be opened to be cleaned.	0.00
3. Repair valves in treatment well so the valve would operate properly.	0.00
<b>COSTS: PART 1 - DREDGING OF INLET</b>	<b>0.00</b>
Mobilization of equipment to site and return,	7,500.00
Daily Cost of 8 Hours	6,900.00
Overtime rate at time and an half per hour over 8 hours	1,293.75
Hopper barge charter rental per day	325.00
(Hopper Barge Charter rental goes from delivery day drop off to being cleaned and returned.)	0.00
Delivery of Empty Hopper Barge	2,800.00
Full barge to unloading facility.....\$4,800.00 - \$6,800.00	0.00
Empty barge back to Tarentum.....\$4,800.00 - \$6,800.00	0.00
Cleaning of Barge (After last unloading and before return)	2,500.00
Unloading of material at deposit site.....\$14,000.00 - \$16,000.00	0.00
Estimated time to load a barge.....3 to 5 days	0.00

Estimated time to unload barge.....	1 to 2 days	0.00
Estimated time in travel.....	6 to 10 days	0.00
Estimate cost per barge.....	\$68,000.00	0.00

---

**COSTS: PART 2 - PUMP HOUSE OUTSIDE WELLS AND/OR MANIFOLD**

Estimated days to clean Well A and B and Video.....	8 - 12 days	0.00
If manifold needs to be isolated by plugs and cleaned: Estimated days.....	TBD	0.00
Custom made plugs.....	\$1,100.00 each	0.00
Bolts/Gasket for manifold.....	TBD	0.00
Silt Bag.....	If Needed/Water - (two will be needed)	0.00

---

**COSTS: PART 3 - REPAIR VALVES IN TREATMENT WELL.**

Estimated days.....	2 - 4 days	0.00
Parts for valves:.....	TBD/UNKNOWN	0.00

---

**DAILY RATES FOR PART 2 AND PART 3**

Daily rate cost for 8 hours	5,280.00
Overtime rate at time and an half per hour over 8 hours	990.00
Only days used will be charged on both proposals.	0.00
Fuel prices could affect pricing on both proposals.	0.00

All Federal, State, or Local permits and licenses needed are the responsibility of the Tarentum Water Treatment Plant. Any and all fines levied in relationship to the above work performed are the responsibility of the Tarentum Water Authority.

This is a Proposal. Final invoicing will occur when the job is finished with the approval of Tarentum Water Plants and Three Rivers Diving LLC.	0.00
---	------

Accepted By

Accepted Date